

## **ADDENDUM NO. 2**

### SPECIFICATION FOR THE RESERVOIR 6 AND ALMOND STREET WATERLINE REPLACEMENT

To: All Prospective Responders

**The following additions and changes are to be made to document Specifications for the Construction of Reservoir 6 and Almond Street Waterline Replacement.**

#### **SPECIFICATIONS**

##### **Section 00 41 43, Article 1, subsection 1.1**

1. Replace entire subsection 1.1 with revised subsection 1.1 in the attachment.
  - a. Replace bid schedule with revised bid schedule (dated 02/09/2026).
    - i. Add bid item no. 6A - Trail Resurfacing with 4" Stabilized Decomposed Granite from Sta. 15+28.58 to Sta. 18+23.88, including remove and replace existing handrail in kind, complete per City of RC Std. Dwg. 1001.

#### **RESPONSE TO QUESTIONS**

1. **Question:** Location for the pipeline at STA 12+69.13 to STA 15+28.58 on Sheet C-1 is inaccessible for the equipment. Does CVWD have an approach for the contractor to access this area for getting the equipment for pipeline installation?

**Response:** It is recommended that the contractor construct a temporary pathway; however, alternative means and methods may be proposed.

2. **Question:** Will CVWD provide the Geotech report for the awarded contractor?

**Response:** A geotechnical report is not available for this project. The contractor should anticipate encountering large rocks and is responsible for removing any rocks with a diameter of 3 inches or greater.

3. **Question:** Will CVWD notify the resident next to 20' equestrian easement regarding the project?

**Response:** CVWD will notify residents through community outreach about the project construction. Contractor is responsible for posting CMS Boards at the job site.

4. **Question:** What are the working hours for this project?

**Response:** Working hours is expected to be from 8:00 a.m. to 4:00 p.m..

5. **Question:** Will CVWD allow the contractor to close the equestrian easement and community trail for the project during construction?

**Response:** The District will work with the City to request closure of the community trail during construction.

6. **Question:** Is D.G. resurfacing required along the trail portion?

**Response:** Yes, trail resurfacing is required from Sta. 15+28.58 to Sta. 18+23.88, with 4" stabilized decomposed granite per City of Rancho Cucamonga Standard Drawing 1001. See revised bid schedule (dated 02/09/2026).

7. **Question:** There is an existing handrail on the trail from Sta. 15+28.58 to Sta. 18+23.88 that may need to be removed and replaced.


**Response:** The existing handrail may be removed and replace in kind. See revised bid schedule (dated 02/09/2026).

**PLEASE SIGN & ATTACH ALL ADDENDA TO YOUR BID.**  
**LAST DAY FOR QUESTIONS: THURSDAY, FEBRUARY 5, 2026, AT 5:00 P.M.**  
**BIDS ARE DUE NO LATER THAN 2:00 P.M. ON THURSDAY, FEBRUARY 12, 2026.**

**Attachments: Revised subsection 1.1 in section 00 41 43, City of R.C. Std. Dwg. 1001**

\*\* END OF ADDENDUM \*\*

Signature: \_\_\_\_\_

  
Tuan Truong, P.E.  
Engineering Manager  
Cucamonga Valley Water District

Date: \_\_\_\_\_

2/9/26

Please sign, date, and include a signed copy with your Bid.

Signature: \_\_\_\_\_

Date: \_\_\_\_\_